

DURBAN'S GAS-TO-ELECTRICITY PROJECT

MITIGATING METHANE EMISSIONS
PARIS, FRANCE

9 NOVEMBER 2015

John Parkin
Deputy Head: Plant & Engineering
eThekweni Municipality

SOUTH AFRICA



**Kwa-Zulu
Natal**

DURBAN (ETHEKWINI)



- Area : 2297 sq kms
- Coast Line: 98 kms
- Rural: 55% by Area
15% by Pop.
- Population : 3,5m
- Households: 925 000
- Unemployment: 32%

SUNSET OVER DURBAN




© Mark Schoombee

NATIONAL GEOGRAPHIC

GLOBAL WARNING

BULLETINS FROM A WARMER WORLD



The New Face of the American Indian 76 Badgers With Attitude 96
Treasure From a Civil War Wreck 108 ZipUSA: Schooled in Tradition 128
PLUS Supplement Map: Indian Country

PROOF OF GLOBAL WARMING



GAS PRODUCTION

“A rule-of-thumb is that 6 – 10m³ of landfill gas will be produced per ton of waste per year for 10 – 15 years from placement”


(Robert Eden, et al; 2002)


- Roughly 500Nm³/hr from every 1m t of waste.
- 1MW electricity from every 700Nm³/hr of gas





AFRICA'S FIRST LANDFILL GAS CDM PROJECT






copyright rickleeks.com



UNSUSPECTING & NAIVE







CHAMPION PASSIONATE



BITTEN OFF MORE THAN WE COULD HANDLE



MARIANHILL LANDFILL



1 MW ENGINE



BISASAR ROAD LANDFILL



COMMISSIONED 6,5 MW JULY 2009





The CDM Project Process

- PIN
- PCN
- Conditional Approval from DNA (DoE)
- Base-Line Study
- Validation Report
- MP (Monitoring Plan)
- PDD (Project Design Document)
- Comment from Public and Stakeholders
- EIA Process and obtain ROD for Project
- Verification of Project
- Final DNA Approval
- Project Registration with CDM Exec Board

PROCESS LIKE A WOLF IN SHEEP'S CLOTHING



LFG-to-Elec CDM Project Time Frames

First contact with PCF/World Bank	November 2001
MOU between eThekweni and PCF –	February 2003
Commence EIA's –	July 2003
Adhoc Approval for funds –	October 2003
ROD's for Mariannahill and La Mercy (“Component One”) –	July 2004
Appeal against “Component One”	August 2004
Appeal response to Minister of DAEA for “Component One” –	September 2004

LFG-to-Elec CDM Project Time Frame Cont

ROD Bisasar (“Component Two”) –	October 2004
Started construction “Component One”	January 2006
Final Revised ROD for “Component Two” (Bisasar) –	August 2006
CDM Registration of Component 1 (Mariannahill & La Mercy) –	November 2006
Commissioning of Mariannahill & La Mercy Flares & Gens –	Nov~Dec 2006
Initial Verification of Mariannahill	January 2007

LFG-to-Elec CDM Project Time Frame Cont

“Component Two” (Bisasar) Start Construction –	March 2007
Verification of “Component 1” Year 1	January 2008
Commissioning of Bisasar Rd Flare & Engines	March 2008
Registration of Component 2 (Bisasar Rd)-	March 2009
Commissioning of 6,5 MW Component 2 (Bisasar Rd)	July 2009
Initial Verification Bisasar	November 2009
2nd Verification Mariannahill	November 2009

LFG-to-Elec CDM Project Time Frame Cont

3rd Verification Mariannahill	September 2011
First Issuance Bisasar (65 711)	30 December 2011
Sale of VCU's (124 884)	January 2012
Commission Gas Chiller	May 2012
First Issuance Mariannahill (39 472)	March 2013
4th & 2nd Verifications Mariannahill & Bisasar	March 2013
2nd , 3rd & 4th Issuance Mariannahill	May, June, Aug 2013

LFG-to-Elec CDM Project Time Frame Cont

Reregistration of Mariannahill Project (ACM 0001)

December 2013

2nd Issuance Bisasar (749 633)

February 2014

5th Verification Mariannahill

March 2014

5th Issuance Mariannahill (33 937)

June 2014

6th Verification Mariannahill, first under ACM 0001

November 2014

No issuance to date

Notification of reregistration for Bisasar

September 2015

Calculated Emission Reductions (in tons)

Site	Methane Destruction	Electricity Generation	TOTALS
Bisasar Road	5,295,296	800,704	6,096,000
Mariannahill	1,112,568	112,344	1,224,912
La Mercy	488,972	24,511	513,483
TOTALS	6,896,836	937,559	7,834,395


THE PARTICIPANTS

- In House Project Management
- World Bank Prototype Carbon Fund
- Department of Trade & Industry
- Department of Energy
- French Development Bank
- EIA Felehetsa / WSP Environmental
- External Verifiers (was SGS then DNV, next?)
- CER Purchaser

THE TEAM

- **Project Management: DSW**
- **Gas Specialist: SLR Consulting (Pty) Ltd**
- **Legal: Imbewu Environmental (Pty) Ltd.**
- **Civil Consultants: Wilson Pass Inc.**
- **Engine Maintenance: Spare Invest 28 cc.**
- **Air Quality Monitoring: SGS SA (Pty) Ltd.**
- **Data Collation & Gas Field : Contra Odour cc**
- **Data Collation & Gas Field: Envitech Solutions**

WHEN THINGS GO WRONG




GAS CHILLER

- DROPPING OUT 95 l/hr







Lynne/Alina 15/100

ADMINISTRATIVE CHALLENGES

- MFMA & SCM don't deal with out of ordinary processes
- EIA Process was problematic
- Registration by UNFCCC Ex Board long, tedious & pedantic
- Inconsistent decisions by Ex Board
- No direct access to Ex Board (recent change)
- Monitoring Onerous, Expensive
- Language is often a barrier
- Drawn out process
- Whole process is costly
- DOE accreditation

TECHNICAL CHALLENGES

- **Lack of Expertise & Resources**
- **Extreme weather conditions**
- **Excess leachate; poorly run site**
- **Manufacturers supplying incorrect equipment**
- **Lack of sharing information**
- **Lack of Experience / Technical Ability**
- **Understanding the Gas Field**


OPERATING CHALLENGES

- **Service Suppliers lack of Expertise**
- **Cost of Spares & Oil**
- **Cost of Services**
- **Availability of Spares**
- **Need good Quality Assurance**
- **Monitoring: correct procedures**
- **Logging of raw data & interpretation**
- **Verification**

LEASONS LEARNED

- Be wary of “Experts”
- Easier to deal with Technical challenges than Political & Administrative issues
- Running of Landfill is as important as the Extraction Process
- Carry out a pre Verification Inspection, saves a lot of stress at verification but not time
- Add 12 months to any time frame given
- Cash flow is a major problem
- CER price has crashed (€15,07 vs €0,22/0,31)

WE'RE STILL LEARNING



**GOOD WORK, BUT I THINK WE
MIGHT NEED JUST A LITTLE
MORE DETAIL RIGHT HERE**



FRUSTRATED



NO CONTROL



OUTWEIGHED



AH ST- - F IT

SHOW ME THE MONEY



Project Review

- The capital and operating expenditures of the project are supported by two revenue streams:
 - Sale of Carbon Credits
 - Sale of Electricity
- Without the sale of carbon credits, the project would not be financially viable.

ELECTRICITY SALES BISASAR

	UNITS	HIGH RATE	AMOUNT	LOW RATE	AMOUNT
PEAK	599429	15,64	93 750,70	5,10	30 570,88
STANDARD	1456209	4,74	69 024,31	3,51	51 112,94
OFF PEAK	1739972	2,57	44 717,28	2,27	39 497,36
SURCHARGE		10,05%	20 852,98		12 178,71
RURAL LEVY		0,45	17 080,25		17 080,25
TOTAL			€245 425,52		€150 440,14

ORIGINAL REFIT (6,13) €232 670,89

CURRENT STATS

- ❖ 7.5 MW Generation of Electricity Capacity
- ❖ Electricity Supply to 3 750 small houses
- ❖ Total LFG Flow ~ 4 400 Nm³/hr at 53% CH₄
- ❖ >20 000 Tons CO₂ equivalent destroyed /month
- ❖ 2,25m tons of CO₂ equivalent destroyed to date
- ❖ > €9,3m worth of electricity generated to date
- ❖ > 315 000 MWh generated
- ❖ > €280 000 electricity income in July 2015

CASH FLOW

INCOME

- ELECTRICITY SALES
- €167 000 / month

- CARBON CREDITS
- €106 300 / month
- €5/CER

- TOTAL
- €3 275 000 / annum

EXPENDITURE

- CAPITAL EXPENDITURE TO DATE € 8 700 000

- ANNUAL OPERATING
- €870 000


Concluding Comments

- Landfill gas offers a viable renewable energy source only when linked to Carbon Finance, CDM or ReBid (R0,079/kWh)
- VER's may be more viable than CER's due to over the top requirements of UNFCCC Process and price
- The EIA process has over-ripened this fruit – lost two years
- Lack of Technical Skills is restricting expansion in Africa
- Implementation of proven technologies is a must
- Distance from Europe is detrimental to fast reaction
- Exchange rate has a dramatic influence on cash flow

Six African projects named among world's 100 most innovative

By: Irma Venter

Published: 27 Aug 12







EXCEEDED EXPECTATION

HOPE THINGS ARE CLEARER



www.dbnlandfillgas2elec.co.za